


Purchasing Office
191 South East Street
Frederick, Maryland 21701
301-644-5208 phone
301-644-5213 fax



Stephen P. Starmer, C.P.M., Purchasing Manager
Kim Miskell, Assistant Purchasing Manager
Billie Laughland, Buyer Specialist
Bill Meekins, Buyer Specialist
Scott Bachtell, Buyer Specialist

ADDENDUM

November 7, 2013

ADDENDUM # 1

RFP 14T5, SCHOOL BUSES

REVISED DUE DATE: FCPS Main Lobby, Thursday, November 21, 2013, prior to and time stamped no later than 2:00 P.M.

This addendum is being issued to provide additions, corrections, clarifications and answers to certain questions raised referencing the original request for proposals.

1. Revised Due Date: ~~2:00 p.m. local time, November 14, 2013~~ **2:00 P.M. local time, Thursday, November 21, 2013.**
2. Page 17, Special Notices, #1. Multi-Agency Participation: “~~Additionally, it is highly recommended by all participating LEA’s that the contract pricing be extended to any independent contractor servicing any public entities within the state of Maryland~~”.
3. In-Service date is defined as the first day the bus is used to transport students.

48 Passenger Bus Specifications:

4. Seating Configuration (8 Rows of Seats)
Rows 1 and 2: shall be integrated child restraint with two positions without lap shoulder belt bolt mounted
Rows 3 – 7: shall be standard 39” bolt mounted seat
Row 8: shall be standard 30” bolt mounted seat
5. Page 22, Axles: 1.3 Conventional:
Front: ~~40,000 (minimum)~~ **Should read: 8,000 (minimum)**
Rear: ~~21,000 (minimum)~~ **Should read: 17,500 (minimum)**
6. Page 22, Battery: 1.4.7: ~~A 150 AMP main circuit breaker with disconnects shall be provided in the engine compartment.~~
7. Page 22, Electrical (Chassis Wiring): 1.10.3 ~~Circuit breakers~~ **Disconnect** of 150 amperes minimum shall be installed between battery and body harness.
8. Page 23, Electrical (Chassis Wiring): 1.10.4 All wiring must be color coded and numbered at ~~4-inch~~ **6-inch** intervals and a diagram of the circuits shall be attached to the body in a readily accessible location.
9. Page 23, Ignition: 1.17.2: Manufacturer shall provide ~~(5)~~ **2** sets of ignition keys per bus (**additional keys added as option on proposal form**).
10. Page 23, Instrument Panel: 1.18.1: Gauges: 11. Diesel Exhaust Fuel Gauge (DEF) - **If Equipped.**
11. Page 24, Tires/Wheels: **Add - 1.24.4: Rims shall be 8 ¼ x 22.5 hub-piloted with five (5) hand holds.**
12. Page 25, Aisle: 1.27.1: One two inch (2”) white rubber aisle strip shall be installed between the two front barriers and one two inch (2”) white rubber aisle strip 27” forward of the emergency door. **Moved to Proposal Sheet as an option.**
13. Page 25, Service Door is changed to read as follows: 1.32.1.2: If the bus is not furnished with an air compressor, an electric door shall be provided at no charge at the customer’s discretion. **Manual door moved to Proposal Sheet as an option.**
14. Page 26, Doors – Heater-Defroster: 1.37.3: Rear ~~70,000~~ **40,000** BTU rear heater behind the rear wheel well on the left side mounted under seat.

